

# THE SWITCH

FUTURE AUTOMATION: the only machine available that can be easily converted

to a labor saving fully automatic on site at a later date

MORE FOR THE MONEY: standard machine wraps heavier, larger loads

USES LESS FILM: advanced film carriage reduces slippage

SAFE & SIMPLE: more superior safety features



Can easily be converted to a fully automatic on site at a later date by installing the unique A-Arm



# THE SWITCH DESIGN FEATURES/SPECIFICATIONS

# **CONTROLS:**

- LCD Operator Interface with Diagnostics
- Cycle Pause & Reinforce Wrap
- ❖ Separate UP/DOWN Spiral Speed Controls
- ❖ 3 Separate Wrap Programs
- Selectable Reduced Film Tension parameters for wrapping top and/or bottom of light loads
- Emergency Stop button
- 4 115 Volts 1 Phase 60 Hz 15 Amps
- 3 Year Warranty on Components

#### **FILM CARRIAGE:**

- ❖ Super Rapid Thread II™ 20" capacity pre-stretch film carriage
- Safety Door with auto power cut-off switch
- Special Film Threading Device Uniquely orientates the sticky side of the film against the pre-stretch rollers and the inside on the load.
- ❖ ½ HP AC variable speed motor
- ❖ 33% to 313% fixed stretch capability
- Carriage Descent Safety Shut-Off Device
- Superior film-to-roller contact area
- Lifetime warranty on pre-stretch rollers

### <u>TOWER DESIGN:</u>

- Fully Enclosed & Guarded Motors
- No Exposed Cables
- Heavy Duty Formed/Structural Steel
- Electro-static powder coated paint finish
- 5 Year Warranty on Steel Fabrications

## **LOW PROFILE TURNTABLE:**

- ❖ 65" diameter
- ❖ 4500# Capacity
- ♦ 1 12 RPM with Soft Start Acceleration
- ❖ ½ HP AC Variable Speed Drive
- Heavy Duty Surround Deck
- Forklift Tubes Front and Rear
- Maintenance Free 48 Support Wheels
- Optional loading ramp 60" long x 48" wide complete with 10" level porch area available



